BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17888

APPROVED SCHEDULE - B

EE/DTP/BBMP/E-PMT/01/2015-16

Improvements to Roads and Drains Laxmi Narayana Temple area Amruthahalli in Ward No 07, Kodigehalli Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NINGANAGOWDA V PATIL		
				In Figures		In Words
1	596.96	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications.	cum	75.0	44772	Rupees Seventy Five Only
2	56.55	KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing	cum	5010.0	283315.5	Rupees Five Thousand Ten Only
3	1053.8	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons.	sqm	232.0	244481.6	Rupees Two Hundred Thirty Two Only
4	72.05	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum)	cum	5840.0	420772	Rupees Five Thousand Eight Hundred Forty Only
5	5.76	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery	TONNE	78000.0	449280	Rupees Seventy Eight Thousand Only
6	4277	KSRRB M300-52.1. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications.	sqm	18.0	76986	Rupees Eighteen Only
7	4277	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery 5	sqm	4.0	17108	Rupees Four Only
8	1069.25	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density	cum	1430.0	1529027.5	Rupees One Thousand Four Hundred Thirty Only
9	4277	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means	sqm	31.0	132587	Rupees Thirty One Only

H.V. 26/2/16

ಸ.ಅ. (ಪೂ.ವ)

Signature of contractor

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NINGANAGOWDA V PATIL		
				In Figures		In Words
10	128.31	KSRRB M500-18. Providing and laying semi dense bituminous concrete25mm to 30mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver	cum	8475.0	1087427.25	Rupees Eight Thousand Four Hundred Seventy Five Only
11	122.2	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications	sqm	475.0	58045	Rupees Four Hundred Seventy Five Only
12	596.96	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	cum	140.0	83574.4	Rupees One Hundred Forty Only
					4427376.25	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
26/2/16

Signature of contractor